BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20445

SCHEDULE-B

NAME OF WORK: Providing and Asphalting to pot holes filling and road cuttings in Dasarahalli Ward no.15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor G N RAMESH		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specfication & as per direction of Engineer-in-charge	Cum	357.85	77.55	Rupees Seventy Seven and Fifty Five Paise Only	27751.27
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	292.93	1598.27	Rupees One Thousand Five Hundred Ninety Eight and Twenty Seven Paise Only	468181.23
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications - Filling pot holes and patch repairs with bituminous concrete, 40mm complete as per specfication & as per direction of Engineer-in-charge	Sqm	1171.8	345.44	Rupees Three Hundred Forty Five and Forty Four Paise Only	404769.32

Signature of the Contractor

Executive Enginee

4	Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 4 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per specfication & as per direction of Engineer-in-charge	Cum	357.85	72.96	Rupees Seventy Two and Ninety Six Paise Only	26108.74
					Total	926810.55
					Percentage	-6.75%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer